





Old Frederick Road Slope Stabilization Project

Public Information Meeting

Thursday, August 22, 2024 | Catonsville Senior Center (501 Rolling Road)

We will begin shortly. The Public Meeting will be recorded.

> Project Team

Baltimore County Department of Public Works and Transportation (BCDPWT)

Nicholas Smith Chief, Structural Design Section

Hiwotie Wondem Project Manager

Johnson, Mirmiran & Thompson, Inc. (JMT) – Prime Consultant AB Consultants, Inc. (ABC) – Sub-consultant

John H. Seifert Project Manager (JMT)


Paul Marotta
 Assistant Project Manager (JMT)

Sanjay Patel Project Manager (ABC)

> Purpose of the Meeting

- 01 Introduce project team
- 02 Present the existing slope condition
- O3 Present the project scope and proposed slope condition
- 04 Present maintenance of traffic during construction
- O5 Present current project cost estimates, funding and schedule
- 06 Obtain community input

> Project Location



> Existing Traffic and Corridor Data

2024 Traffic Counts

Approximately 2,214 vehicles/day during weekdays

Posted Speed Limit


- 25 MPH
- 20 MPH advisory speed around curve

Posted Weight Restriction

No Thru Traffic over 5 Tons

Accident Data

Minimal crash history within project vicinity



> Existing Condition

Roadway

- Two lane road
- Roadway width varies between 17 and 20ft
- Narrow lane widths
- Temporary barrier and slope encroaching on roadway
- Drainage inlets north and south of barrier

Benjamin Banneker Park Red Trail

Trail location beyond limits of slope stabilization

Subsurface

Residual soil, decomposed rock and bedrock layers



Description	Chepth	Semple	Blown/1.75 inch	Recovery (inches)	Remerka	(i)	WelscCaved Depth (f)	Description	Depth	Semoler	Number	Blows/1.75 Inch	Recovery (Inches)	Romanio
					1 inches of lopeol.	283			-	,	H		Н	Other 10' SW of B-5.
Light brown, moist, loose, sifty SAND (Residual Soll).	1	6-1	3-3-3	٠		261	U	Refer to Boring B-G for description of meterial evacuationed from 0.611.71	1	L		mer.	١.	7 Inches of Asptait Pave August Wheel (D 2 See).
Light brown, moist, medium dense, eithy SAND	1.4		81819	18		200		Light gray, dry, very dense, sity SAND, with rock fragmants (Decomposed Rock).	40	Г	9-2	807	١,	Administration of a sec.
(Fantidual Soll).	- 6	~	0.0.9			279-		Bottom of Boring @ 2.1 ft	Ė,	,				
Light brown / brown, dry, dense, elity SAND, trace rock imprests (Hestikasi Sal).	1.1	9-3	12-13-19	18	Suit and sample collected from 1 I 10 feet.	277-			ŀ	L				
	H					779				П				
Light brown / Invene, dry, dames, elliy SAND, trace nock fragments (Residual Soli). Light brown / brown, dry, very dames, elliy SAND, brace nock fragments (Residual Solf).	1	94	17 + 94 + 95	16		274			ŀ	ı				
	F."	7				273-			- "	1				
	H					271			-					
	1					270			ŀ					
	- 15	0.0	13 - 19 - 34	12		200-			Ĺ,	,				
	H					267			-					
Light gray / brown, dry, very donse, sity SAND, with rock fragments (Decomposed Rock).	1					205-			ŀ					
	1	0-0	OLT.	2		284			-					
Light gray / brown, dry, very dense, sity ROCK FRAGMENTS, with cond (Decomposed Rock).	- 20	6.7	507*	1	Appropriate Approp	203			- 20	•				
GPANITE, moderately weathered, medium hard to hard, jointed @ 81 degree, tanigrayipink.	1	ш				262			Ī					
	H	RC-		-6	RBC+72%, RQD+62%	280			ŀ					
	Lz	ш				259-			Ė,					
GRANTE, modurately swalfwred, medium hard to herd, joined @ 40, 52 & 55 segmes, tankgray/plate.	1	Н				257			1	Т				
	1			١.	BECYTON, BODINSON,	200-			ŀ					
	[]	RC-		44	NBC+75%, HGDH00%.	254			[
	- 30	Ш			Installed temporary oming at 20 2 lest.	253	1		- x	>				
Boltom of Boring @ 30.6 ft	1					222-			- 1					

> Slope Failure Event

Severe Rain Event

- Spring 2018
- Flooded nearby Ellicott City
- 8 inches in about 2 hours
- Significant erosion
- Steep hillside sloughed into roadway
- Temporary barrier placed
- Relocated existing Red Trail



Existing Slope Deterioration







Steep hillside overhanging roadway

Uprooted tree up slope due to erosion


Uprooted tree adjacent to abandoned trail

> Alternative Analysis Study

Total Approved Project Budget: \$1.14 Million Phase 1 - Alternative Analysis Study

- Traffic Impact and Detour Study
- Tree Identification and Delineation Memorandum
- Water Resources Design Memorandum
- Studied five slope stabilization alternatives
 - Three retaining wall options
 - Two barrier wall options
- Studied three roadway alternatives
 - Two Lanes
 - One Lane with bike lanes
 - One Lane with reduced shoulder
- Barrier wall with one lane and reduced shoulder was determined to be the only viable option with the available budget

Next Phase - Final Design and Construction



> Project Scope

Proposed Improvements


- Slope Stabilization
- Landscaping
- Construction of new permanent traffic barrier

Repaving of roadway

Roadway restricted to One Way

Modification to the south

drainage inlet



> Proposed Barrier Wall




Existing ConditionTwo lane road with temporary barrier

Photograph taken looking from Old Frederick Rd towards Frederick Rd




Proposed RenderingOne lane road with permanent barrier

> Proposed Barrier Wall Plans



> Proposed Barrier Wall Plans



Standard 42" Maryland Barrier

> Barrier Wall Finish Options



Smooth Concrete Finish



Stamped Form Liner Finish
Stained to match surrounding rock



Sample Finish

Forest and Tree Impact

Forest Stand 1

- Fair to poor condition with signs of disease
- Abundance of invasive species
- No specimen or state champion trees identified
- Baltimore County Environmental Impact Review Permit required for disturbance

Roadside Trees

 Maryland Department of Natural Resources Permit required for disturbance

Tree Removal

Estimated approximately 70 trees to be removed

Landscaping Proposed on Slope



Proposed Traffic Pattern

One Way Traffic

- Conducted NE and SW directional traffic analysis
- Similar, acceptable traffic operations
- MD 144 provides a left turn bypass lane for NE bound traffic (not provided at Oella Ave)
- Recommended
 Direction of Traffic:
 NE bound traffic from
 Old Frederick Road to
 Bryans Mill Way



Maintenance of Traffic During Construction

Detour Route

- Old Frederick Road
 Oella Avenue –
 Frederick Road
- 3-minute travel time
- 1 mile long
- Acceptable traffic operations along detour route



Current Project Cost Estimates and Funding

Project Status

- Preliminary Design Stage (30% Level of Completion)
 - Alternative Analysis Study complete

Project Funding

Baltimore County FY24 Capital Budget

Construction Cost Estimate

\$850,000 Construction and Construction Management Cost (Funded)

> Project Schedule









Alternative
Analysis Study
Complete

August 2024

Design Complete

December 2025

Begin Construction

Late Spring 2026 (Tentative)

End Construction

Late Fall 2026 (Tentative)

Next Step and Community Input

Proceed with Final Design based on

- Feedback from the community
 - Tonight's feedback
 - Email to oldfrederickroad@baltimorecountymd.gov

Final Design Milestones

- Permitting Approvals
- Concurrence with:
 - Baltimore County Department of Recreation and Parks
- Final Design Complete

For Project Information

Contact us:

Hiwotie Wondem

BCDPWT Project Manager Towson, Maryland 410-887-3737 oldfrederickroad@baltimorecountymd.gov

Access project webpage:

https://www.baltimorecountymd.gov/departments/public-works/engineering/projects







Webpage



Questions?